

Project: Hollingworth Elementary Asphalt Jogging Track Replacement

Location: 3003 East Hollingworth, West Covina, CA 91792

General Description/Scope of Work:

Option # 1

- *Remove and dispose of approximately 22, 200 square feet of existing asphalt.*
- *Remove and dispose of approximately 3000 linear feet of existing redwood 2 x 4 headers.*
- *Grade & compact area to receive 3" of Class II CMB, haul-off excess dirt.*
- *Construct approximately 3,000 linear feet (total) of 4" wide, new, concrete mow curb at inner and outer edges of new asphalt paving*
- *Construct 3"AC over 3"of compacted Class II CMB*
- *Layout & stripe track [4 lanes, each 3'-6" wide].*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation.*

Option # 2

- *Pulverize (recycle) existing asphalt and use in lieu of Class II CMB. Haul away excess dirt and surplus pulverized asphalt; all else remains the same as Option #1, above.*

Notes:

Dimensions and quantities indicated above are for reference ONLY. Contractors bidding said project are responsible for field verifying all dimensions and quantities shown.