

**Addendum #2 - Revision to drawing and item #7**

# **Rowland Unified School District**

## **Rowland High School**

### **Scope of work for fence replacement**

**Scope of work:** Renovate approx. 1,031 of chain link fencing and 6 gates. Around the tennis courts. With 1" 9 Gauge black vinyl fence

**See attached specs.**

Install 1" 9 gauge black vinyl fence

- 1) Remove and dispose of existing chain link approx. 1,031 linear ft. and on 6 gates.
- 2) Straighten out 3 12ft post
- 3) Adjust top, middle and bottom rails as needed,
- 4) Paint all post, rails (top, middle, and bottom) and gates with black galvanized paint,
- 5) Re-stretch new bottom tension wire where needed,
- 6) Replace tension bars also black, and paint tension bands,
- 7) Install new 11 gauge core 9 gauge 1 inch black vinyl fence approximate 1,031 linear feet and 5 gates.

**All work to be completed in a workman like manner according to standard practices, any alterations or deviations from above specifications involving extra cost must be in writing to a school district supervisor,**

**All work to be completed within 30 calendar days from the day from Notice to proceed,**

**Any questions please call Danny Romo (626) 712-7279**

# ROWLAND HIGH SCHOOL TENNIS COURTS

