

Project: [Ybarra Academy – Drop-off Driveway Asphalt Replacement](#)

Location: 1300 Brea Canyon Cut-Off Road, Walnut, CA 91789

General Description/Scope of Work:

Drop-Off Driveway:

- *Remove and dispose of approximately 7,700 square feet of existing asphalt pavement.*
- *Grade & compact area to receive 4" of 1/2" aggregate, hot-mix-asphalt [HMA] paving, over 6" of compacted Class II CMB. Haul-off excess dirt and/or related materials, as needed.*
- *Install approximately 220 linear feet of 4" wide x 8" deep, concrete mow curb, where new asphalt paving meets edge of turf.*
- *Place 4" of 1/2" HMA over 6" of compacted Class II CMB*
- *Stripe driveway as needed.*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation.*

Main Parking-Lot:

- *Remove, and dispose of approximately 24 concrete wheel-stops.*
- *Remove and dispose of approximately 1400 square feet of existing concrete paving.*
- *Grade and compact designated trash truck apron area (approximately 1800 square feet) to receive 6" of 3000psi CONCRETE over 6" of compacted Class II CMB. Haul-off excess dirt and/or pulverized material as needed.*
- *Place approximately 1800 square feet of 3000psi concrete, with #4 rebar at 18" centers, in each direction, over 6" of compacted Class II CMB. Concrete to be broom finished. Area as determined by District.*
- *Pulverize and leave in place, for use as base material, approximately 24,000 square feet of existing asphalt pavement.*
- *Grade and compact pulverized material to receive 4" of 1/2" aggregate, hot-mix-asphalt [HMA] paving. Haul-off excess dirt and/or pulverized material as needed.*
- *Install 2" x 4" redwood header as needed.*
- *Place 4" of 1/2" HMA paving over graded and compacted pulverized material base.*
- *Stripe playground as needed.*
- *Install new concrete wheel-stop as needed.*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation*

Notes:

Contractor is responsible for the removal & re-installation of sign post & benches (where applicable)

Dimensions and quantities indicated above are for reference ONLY. Contractors bidding this project are responsible for field verifying all dimensions and quantities shown.