

Project: Hurley Elementary Playground - Asphalt Replacement

Location: 535 South Dora Guzman Avenue, La Puente, CA 91744

General Description/Scope of Work:

Main Playground:

- *Pulverize and leave in place, for use as base material, approximately 42,000 square feet of existing asphalt pavement.*
- *Remove and dispose of approximately 400 linear feet of existing redwood 2 x 4 headers.*
- *Grade & compact pulverized material to receive 3" of 1/2" aggregate, hot-mix-asphalt [HMA] paving. Haul-off excess dirt and/or pulverized material as needed.*
- *Install approximately 400 linear feet of 2"x 4" redwood header, where new asphalt paving meets edge of turf.*
- *Place 3" of 1/2" HMA paving over graded and compacted pulverized material base.*
- *Stripe playground as needed.*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation.*

Notes:

Dimensions and quantities indicated above are for reference ONLY. Contractors bidding this project are responsible for field verifying all dimensions and quantities shown.